



REPUBLIC OF THE PHILIPPINES
DEPARTMENT OF SCIENCE & TECHNOLOGY
PHILIPPINE SCIENCE HIGH SCHOOL-SOCCSKSARGEN REGION CAMPUS
Brgy. Paraiso, City of Koronadal

Project: **CONSTRUCTION OF THE ADMINISTRATION BUILDING II**
Subject: Bid Form
Bidder's Name:
Bid Amount:
Date Submitted:

ITEM	SCOPE OF WORK	QTY	UNIT	UNIT COST	TOTAL COST
1.0	GENERAL REQUIREMENTS				
	1.1 Mobilization/Demobilization	1	lot		
	1.2 Bonds, Insurances & Permits	1	lot		
	1.3 As built plans	1	lot		
	1.4 Temporary Utilities (Electricities & Water)	1	lot		
	1.5 Temporary Facilities				
	1.5.1 Temporary Warehouse	1	lot		
	1.5.2 Field Office/Conference Room	1	lot		
	1.5.3 Temporary Fence/Site Enclosure	1	lot		
	1.6 Surveying & Layouts	1	lot		
	1.7 Testing of Materials				
	1.7.1 Compression Testing (Cylinder, CHB, Mortar)	1	lot		
	1.7.2 Cement (Physical & Chemical Properties)	1	lot		
	1.7.3 Complete Test for Aggregates (Grading, Soundness, Abrasion, Specific Gravity, Unit Weight, Absorption)	1	lot		
	1.7.4 Tensile Properties of Rebars & Steeldecking	1	lot		
	1.7.5 Design/Trial Mix	1	lot		
	1.7.6 Curing Tank & Curing Materials	1	lot		
	1.8 Construction Safety/PPEs	1	lot		
	SUB-TOTAL 1.0				
2.0	LAND DEVELOPMENTS				
	2.1 Excavation	1	lot		
	2.2 Earthfill				
	2.2.1 filling materials	119.00	Cu.M.		
	2.3 Entrance Porch 5" Concrete Pavement 12 sq.mtrs				
	2.3.1 Type 1 Portland Cement	13.50	bags		
	2.3.2 Washed and screened Sand	0.80	Cu.M.		
	2.3.3 Gravel	1.50	Cu.M.		
	2.3.4 12mm def bars grade 40	151.00	kgs		
	2.3.5 Ga 16 tie wire	19.00	kgs		
	SUB-TOTAL 2.0				
3.0	FORMWORKS AND SCAFFOLDINGS				
	3.1 Formworks and scaffoldings				
	3.1.1 form lumber	5,000.00	bd ft		
	3.1.2 1/4" x4x8	220.00	pcs		
	3.1.3 assorted conc nails	200.00	kgs		
	3.1.4 steel scaffolding	1.00	lot		
	SUB-TOTAL 3.0				
4.0	STRUCTURAL WORKS				
	4.1 Reinforced Concrete Footing				
	4.1.1 Type 1 Portland Cement	477.00	bags		
	4.1.2 Washed and screened Sand	26.50	Cu.M.		
	4.1.3 Gravel	53.00	Cu.M.		
	4.1.4 16mm def bars grade 40	2,617.00	kgs		
	4.1.5 Ga 16 tie wire	41.00	kgs		
	4.2 Reinforced Concrete Tie Beam				
	4.2.1 Type 1 Portland Cement	153.00	bags		
	4.2.2 Washed and screened Sand	8.50	Cu.M.		
	4.2.3 Gravel	17.00	Cu.M.		
	4.2.4 20mm def bars grade 40	2,816.00	kgs		
	4.2.5 16mm def bars grade 40	360.25	kgs		
	4.2.6 10mm def bars grade 40	391.05	kgs		
	4.2.7 Ga 16 tie wire	11.00	kgs		
	4.3 Reinforced Concrete Wall Footing				
	4.3.1 Type 1 Portland Cement	63.00	bags		
	4.3.2 Washed and screened Sand	3.50	Cu.M.		

		4.3.3	Gravel	7.00	Cu.M.		
		4.3.4	12mm def bars grade 40	421.90	kgs		
		4.3.5	Ga 16 tie wire	11.00	kgs		
	4.4	Reinforced Concrete slab on fill and suspended slab					
		4.4.1	Type 1 Portland Cement	720.00	bags		
		4.4.2	Washed and screened Sand	40.00	Cu.M.		
		4.4.3	Gravel	80.00	Cu.M.		
		4.4.4	12mm def bars grade 40	8,053.00	kgs		
		4.4.5	Ga 16 tie wire	165.00	kgs		

	4.5	Reinforced Concrete Columns				
	4.5.1	Type 1 Portland Cement	558.00	bags		
	4.5.2	Washed and screened Sand	31.00	Cu.M.		
	4.5.3	Gravel	62.00	Cu.M.		
	4.5.4	20mm def bars grade 40	13,456.60	kgs		
	4.5.5	16mm def bars grade 40	1,422.00	kgs		
	4.5.6	12mm def bars grade 40	2,243.00	kgs		
	4.5.7	10mm def bars grade 40	3,093.00	kgs		
	4.5.8	Ga 16 tie wire	504.00	kgs		
	4.6	Reinforced Concrete Beams and girders				
	4.6.1	Type 1 Portland Cement	612.00	bags		
	4.6.2	Washed and screened Sand	34.00	Cu.M.		
	4.6.3	Gravel	68.00	Cu.M.		
	4.6.4	25mm def bars grade 40	2,703.00	kgs		
	4.6.5	20mm def bars grade 40	7,602.70	kgs		
	4.6.8	10mm def bars grade 40	1,351.00	kgs		
	4.6.9	Ga 16 tie wire	150.00	kgs		
	4.7	Reinforced Concrete Stairs				
	4.7.1	Type 1 Portland Cement	216.00	bags		
	4.7.2	Washed and screened Sand	12.00	Cu.M.		
	4.7.3	Gravel	24.00	Cu.M.		
	4.7.4	16mm def bars grade 40	2,976.80	kgs		
	4.7.5	Ga 16 tie wire	36.00	kgs		
	4.8	Reinforced Concrete Gutters				
	4.8.1	Type 1 Portland Cement	22.50	bags		
	4.8.2	Washed and screened Sand	1.25	Cu.M.		
	4.8.3	Gravel	2.50	Cu.M.		
	4.8.4	12mm def bars grade 40	64.50	kgs		
	4.8.5	Ga 16 tie wire	1.50	kgs		
	4.9	Reinforced Concrete Window Canopies				
	4.9.1	Type 1 Portland Cement	94.00	bags		
	4.9.2	Washed and screened Sand	5.18	Cu.M.		
	4.9.3	Gravel	10.35	Cu.M.		
	4.9.4	12mm def bars grade 40	270.00	kgs		
	4.9.5	Ga 16 tie wire	6.50	kgs		
		SUB-TOTAL 4.0				
5.0	STEEL WORKS					
	5.1	Steel Works (Trusses & Entrance Canopy)				
	5.1.1	6mmx2"x2" angle bar	96	lght		
	5.1.2	4.5mmx1-1/2"x1-1/2" angle bar	2	lght		
	5.1.3	1.50mm 2x6 Cee Purlins	22	pcs		
	5.1.4	16mm x6m plain round bars	6	length		
	5.1.5	Sag Rod (Plain Round Bar, 10mm)	7	length		
	5.1.6	Turn Buckle (1/2"x1')	12	pcs		
	5.1.7	welding rods (N90)	40	kgs		
	5.1.8	ms plate 0.8mm	1	pc		
	5.1.9	rectangular tubing1.5mmx2x4x6m	10	length		
	5.1.10	hilti bolt 16mm	18	pcs		
	5.2	Roofing				
	5.2.1	0.5mm ribbed type color bonded G.I. Rfg sheets	133	L.M.		
	5.2.2	0.5mm colorbonded wall flashing x8'	10	pcs		
	5.2.3	0.5mm colorbonded end flashing x8'l	3.5	pcs		
	5.2.4	0.5mm colorbonded gutter 0.25x0.30m x2.40m	8	pcs		
	5.2.5	sealant	3	tubes		
	5.2.6	Tek Screw & Rivets	10	Kgs		
	5.2.7	Touch up Paint	1	gal		
	5.2.8	solid polycarbonate sheets	120	sq.mt		
	5.3	Railings (stairs and ramp)				
	5.3.1	Stainless Pipe (3"x6m, S-20)	8	Length		
	5.3.2	Square tubing (1- 3/4")	4	Length		
	5.3.3	flat bar 1/4" x 1-1/2"x6m	22	pcs		
	5.3.4	Welding Rod (Stainless)	20	kgs		
	5.4	Railings (Parapet)				
	5.4.1	aluminum tubular railing 2"x2"x6m	34	Length		
	5.4.2	aluminum tubular railing 2"x4"x6m	5	Length		
		SUB-TOTAL 5.0				
6.0	MASONRY WORKS					
	6.1	Concrete Hollow Block Walls (6" for toilet walls)				
	6.1.1	CHB 6" (350 psi)	2500	Pcs		
	6.1.2	Cement (40 Kgs)	160	Bags		

		6.1.3	Washed Sand	8.75	Cu.M.		
		6.1.4	DRB 10mm, Grade 40	82.5	Kgs		
		6.1.5	G.I. Wire (G-16)	6.5	Kgs		
	6.2	Concrete Hollow Block Walls (4") (Exterior and Interior Walls)					
		6.2.1	CHB 4" (350 psi)	10,016	Pcs		
		6.2.2	Cement (40 Kgs)	654	Bags		
		6.2.3	Washed Sand	36	Cu.M.		
		6.2.4	DRB 10mm, Grade 40	331	Kgs		
		6.2.5	G.I. Wire (G-16)	27	Kgs		

	6.3	Catch Basins				
	6.3.1	CHB 4" (350 psi)	100	Pcs		
	6.3.2	Cement (40 Kgs)	8	Bags		
	6.3.3	Washed Sand	0.5	Cu.M.		
	6.3.4	DRB 10mm, Grade 40	5	Kgs		
	6.3.5	G.I. Wire (G-16)	0.5	Kgs		
	6.4	Plastering (25 mm thick)(Exterior and Interior Walls)				
	6.4.1	Cement (40 Kgs)	520	Bags		
	6.4.2	Washed Sand	150	Cu.M.		
	6.5	Concrete Hollow Block Walls (6") below NGL				
	6.5.1	CHB 6" (350 psi)	2113	Pcs		
	6.5.2	Cement (40 Kgs)	136	Bags		
	6.5.3	Washed Sand	7.4	Cu.M.		
	6.5.4	DRB 10mm, Grade 40	82.57	Kgs		
	6.5.5	G.I. Wire (G-16)	5.5	Kgs		
		SUB-TOTAL 6.0				
7.0		PAINTING WORKS				
	7.1	Wall painting (3 semi gloss latex coats)	828.00	Sq.M.		
	7.2	Ceiling painting (flat latex white finish)	583.20	Sq.M.		
	7.3	Painting of wooden doors and jambs (tile gloss finish)	13.00	sets		
		SUB-TOTAL 7.0				
8.0		TILEWORKS				
	8.1	Main flooring(0.60mx0.60m) Matte Porcelain tiles	447.88	Sq.M.		
	8.2	External porch, and ramp (0.60mx0.60m) Granite Tiles non skid	40.88	Sq.M.		
	8.3	Stairs & Landing (30x30) Ceramic Tiles non skid	74.50	Sq.M.		
	8.4	Comfort rooms wall (30x60) ceramic Tiles (1.5m height)	173.50	Sq.M.		
	8.5	Comfort rooms floor (30x60) ceramic Tiles	47.72	Sq.M.		
	8.5	Ramp Tiles .30x.60m	6.60	Sq.M.		
	8.6	Brass nosing 1"x2"x6m	44.00	pcs		
	8.7	Vinyl flooring (child minding)	12.92	Sq.M.		
	8.8	roof deck (0.60mx0.60m)	113.98	Sq.M.		
		SUB-TOTAL 8.0				-
9.0		CEILING				
	9.1	Hardiflex Ceiling				
	9.1.1	Hardiflex 5mmx4x9	583.20	Sq.M.		
	9.1.2	Metal Frames	583.20	Sq.M.		
	9.1.3	perforated upvc ceiling soffits on metal furrings	36.00	Sq.M.		
		SUB-TOTAL 9.0				
10.0		PLUMBING WORKS				
	10.1	FRESH WATER LINES				
	10.1.1	PPR Pipes (1"), PNS 16	12	Lengths		
	10.1.2	PPR Pipes (1-1/4"), PNS 16	10	Lengths		
	10.1.3	PPR Pipes (1/2"), PNS 16	6	Lengths		
	10.1.4	PPR Pipe Fittings (Elbows, Tees, Reducers, etc)	1	Lot		
	10.1.5	Consumables (Teflon, Cement Solvent, etc.)	1	Lot		
	10.2	SANITARY & DRAINAGE LINES				
	10.2.1	PVC Pipe 4", Series 1000	20	Lengths		
	10.2.2	PVC Pipe 2", Series 1000	12	Lengths		
	10.2.3	PVC Pipe Fittings (Elbows, Wyes, Tees, Cleanouts, etc)	1	Lot		
	10.2.4	Consumables (Teflon, Cement Solvent, etc.)	1	lot		
	10.3	STORM DRAIN				
	10.3.1	PVC Pipe (4", S-1000)	30	Length		
	10.3.2	PVC Pipe (6", S-1000)	31	Length		
	10.3.3	PVC Pipe Fittings (Elbows, coupling, etc)	1	Lot		
	10.4	PLUMBING ACCESSORIES				
	10.4.1	Stainless Floor Drain	11	Pcs		
	10.4.2	Tissue Holder	9	Pcs		
	10.4.3	Soap Holder	2	Pcs		
	10.4.4	Liquid soap dispenser	8	Pcs		
	10.4.5	Ball Valves	10	Pcs		
	10.4.6	slop sink wall faucet	2	pcs		
	10.5	PLUMBING FIXTURES				
	10.5.1	Water Closet	9	Sets		
	10.5.2	counter top Lavatory with faucet	2	Sets		
	10.5.3	wall hung lavatory	7	set		
	10.5.4	Urinal	2	Sets		
	10.5.5	stainless steel kitchen sink single bowl with faucet	3	set		
	10.5.6	Shower valve and Head	2	sets		
	10.5.7	slop sink	2	set		
		SUB-TOTAL 10.0				

11.0	ELECTRICAL & AUXILIARY WORKS					
	11.1	Lighting and Power distribution				
		11.1.1	THHN Copper Wire 10/7	3	rolls	
		11.1.2	THHN Copper Wire 12/7	5	rolls	
		11.1.3	THHN Copper Wire 14/7	4.5	rolls	
		11.1.4	PVC Conduit 1/2, S-40	150	Length	
		11.1.5	PVC Conduit 2-1/2", S-40	7	Length	
		11.1.6	PVC elbow 1/2, S-40	120	pcs	
		11.1.7	PVC elbow 2-1/2", S-40	3	pcs	
		11.1.8	metal Junction Box (4X4,)	65	Pcs	
		11.1.9	metal Utility Box (2x4)	25	Pcs	
		11.1.10	metal Square BOx with cover	8	Pcs	
		11.1.11	metal Pull box 4x12x12	2	Pcs	
		11.1.12	wire gutter 5x12x48	1	Pcs	
		11.1.13	Convenience outlet 2 gang	65	sets	
		11.1.14	aircon outlet 1 gang	11	sets	
		11.1.15	Emergency Light Outlets	30	sets	
		11.1.16	LED exit sign outlets	4	sets	
		11.1.17	Switch 1 gang	22	sets	
		11.1.18	Switch 2 gang	11	sets	
		11.1.19	Switch 3 gang	2	sets	
		11.1.20	Switch 3 gang 3 way	2	sets	
		11.1.21	magnetic switch 3HP	11	sets	
		11.1.22	fitting connectors etc.	1	lot	
		11.1.23	tapes , solvent cement	1	lot	
	11.2	Electrical Fixtures				
		11.2.1	LED glass covered Pinlights 4" with 12 watts bulb	157	Sets	
		11.2.2	emergency light	30	sets	
	11.3	Breakers and Panel boxes				
		11.3.1	PB-1 Panel Box 3 phase bolt on industrial type center main 12 branches with 100Amps Main; 4-15amps; 2-20amps; 6-30amps	1	set	
		11.3.2	PB-2 Panel Box 3 phase bolt on industrial type center main 12 branches with 100Amps Main; 3-15amps; 3-20amps; 6-30amps	1	set	
		11.3.3	PB-3 Panel Box 3 phase bolt on industrial type center main 6 branches with 60Amps Main; 2-15amps; -20amps; 3-30amps	1	set	
		11.3.4	MDP Panel Box industrial type 3phase center main bolt-on; 200Amp main	1	set	
		11.3.5	50mm THHN wire	40	mtrs	
		11.3.6	14mm THHN wire	20	mtrs	
		11.3.7	8.0mm THHN wire	20	mtrs	
		11.3.8	service entrance wiring	1	lot	
		11.3.9	Entrance Cap	1	pc	
		11.3.10	Male adaptor	1	pc	
		11.3.11	HD secondary rack	1	set	
		11.3.12	U-bolt connector	3	pcs	
		11.3.13	rubber tape	3	rolls	
		11.3.14	Conduits and Fittings	1	lot	
SUB-TOTAL 11.0						
12.0	ELECTRONICS AND COMMUNICATION					
	12.1	Fire Detection and Alarm System (FDAS)				
		12.1.1	Fire Alarm control panel 4 zones	1	set	
		12.1.2	FDAS Wired smoke detector	29	unit	
		12.1.3	fire alarm siren with stobe LED light	4	unit	
		12.1.4	manual station break glass	4	unit	
		12.1.5	Cables Tray, wires, PIPINGS, etc	1	lot	
	12.2	Audio and Video				
		12.2.1	Power amplifier 500amps	1	unit	
		12.2.2	Pre amplifier mixer 8 mic output	1	unit	
		12.2.3	speaker wall mounted 100 amps	4	units	
		12.2.4	speaker stand alone 500 amps	2	units	
		12.2.5	cables/wires/speaker wires/ pipings etc	1	lot	
	12.3	CCTV				
		12.3.1	DVR (16 inputs) full HD, USB, Network) or higher	1	unit	
		12.3.2	1080p indoor/outdoor Camera or higher	10	unit	
		12.3.3	4 terabyte hard disk (SATA)	2	unit	
		12.3.4	LCD Monitor 32"	5	units	
		12.3.5	Centralized power supply 12v/30amp	1	unit	
		12.3.6	cables/wires/siamese etc	1	lot	
	12.4	Local area network (LAN)				
		12.4.1	access point (wifi)	3	units	
		12.4.2	1/0 with 2 gang and face Plate	11	units	

		12.4.3	Cables/Wires (Cat 5E/6)	1	lot		
	12.5	Telephone					
		12.5.1	single line telephone set	12	unit		
		12.5.2	SLA Krone Terminal Block 10 pairs	2	unit		
		12.5.3	I/O for telephone outlet	12	units		
		12.5.4	cables/wires/telephone wires/Cat 5e/6/ pipings etc	1	lot		
	12.6	Grounding System					
		12.6.1	Ground Bus Bar (1/4"x1"x12")	1	pc		
		12.6.2	Bronze Ground Rod 3 meters	2	pc		
		12.6.3	AWG no. 4	12	mtrs		
	12.7	Auxiliary Equipment					
		12.7.1	Automatic Voltage Regulator	1	pc		
		12.7.2	Uninterrupted Power Supply	1	pc		
		12.7.3	Exit Signs	4	units		
			SUB-TOTAL 12.0				

13.0	GLASSWORKS					
	13.1	W-01 Powder coated sliding aluminum windows with clear float with fixed glass panels 4.48mx3.00m	1	Set		
	13.2	W-02 Powder coated sliding aluminum windows with clear float with fixed glass panels 1.50mx3.00m	1	Set		
	13.3	W-03 Powder coated sliding aluminum windows with clear float with fixed glass panels 1.80mx3.00m	4	Sets		
	13.4	W-04 Powder coated sliding aluminum windows with clear float 1.50 mx1.25m	14	Sets		
	13.5	W-05 awning window with clear glass on pc-white aluminum white tubular 2.60mx0.50m	1	Sets		
	13.6	W-06 awning window with clear glass on pc-white aluminum white tubular 1.60mx0.50m	3	Sets		
	13.7	W-07 awning window with clear glass on pc-white aluminum white tubular 0.50mx0.50m	2	Sets		
	13.8	W-08 analog aluminum louver window 1.50mx2.6 0m	1	Set		
	13.9	W-09 analog aluminum louver window 1.35mx2.40m	2	Sets		
	13.7	W-10 analog aluminum louver window 1.35mx2.605m	3	Sets		
	13.8	DW-1 Double Leaf Swing Door on PC white FD Sections with fixed sidelights and transom overall size 3.85mx3.00m	1	Set		
	13.9	DW-2 Fixed Glass Sidelight on Powder coated white aluminum windows with 1/4" clear float 0.80mx2.10 m	1	Set		
	13.18	D-03 Glass swing door using 10mm clear glass on FD Section on pc white aluminum frame overall size 0.90mx2.10m	8	Sets		
	13.19	D-06 Glass swing door using 10mm clear glass on FD Section on pc white aluminum frame overall size 0.80mx2.10m	4	Set		
	13.20	Mirror with plyboard backing (floating) 0.80mx1.20m	1	set		
	13.21	Mirror with plyboard backing (floating) 0.80mx0.60m	5	set		
SUB-TOTAL 13.0						
14.0	WATERPROOFING					
	14.1	Waterproofing of toilet & pantry floors (2nd and 3rd)	35	sq.mt		
	14.2	Waterproofing of deck floors	124.24	sq.mt		
SUB-TOTAL 14.0						
15.0	TERMITE CONTROL					
	15.1	Soil Poisoning	230	sq.mt		
SUB-TOTAL 15.0						
16.0	THERMAL CONTROL					
	16.1	Insulation	133	sq.mt		
SUB-TOTAL 16.0						
17.0	ARCHITECTURAL SPECIALTIES					
	17.1	Modular toilet cabinets made from laminated phenolic board on an stainless steel tubular	2	Sets		
	17.2	Sashworks				
	17.2.1	D-01 Hollow Core Laminated flushed Door with side leaf 1.20mx2.10m on	1	sets		
	17.2.2	D-02 Hollow Core Laminated flushed Door 0.90mx2.10m on 2"x6" wooden	5	sets		
	17.2.3	D-05 Hollow Core Laminated flushed Door 0.80mx2.10m on 2"x6" wooden	3	sets		
	17.2.4	D-09 Hollow Core Laminated flushed Door 0.70mx2.10m on 2"x6" wooden	1	set		
	17.2.5	D-10 twin leaf Aluminum Louver Door 1.00mx2.10m with 2"x6" wooden Jamb	2	sets		
	17.2.6	D-11 twin leaf laminated flush Door 0.80mx2.10m with 2"x6" wooden Jamb	1	sets		
	17.2.7	D-04 upvc Door industrial type 0.90m x2.10m	1	set		
	17.2.8	D-07 upvc Door industrial type 0.80m x2.10m	9	sets		
	17.2.9	D-08 upvc Door industrial type 0.70m x2.10m	4	sets		
	17.3	Door Lockset				
	17.3.1	Lever Type Satin Finished Door Lockset	25	sets		
	17.4	ACP CLADDING (Façade and Entrance Canopy)				
	17.4.1	aluminum composite wall panel	50	Sqmt		
SUB-TOTAL 17.0						
18.0	SINK COUNTER TOPS					
	18.1	Sink Counter tops				
	18.1.1	Clinic sink counters 0.60x1.80m granite tile finish with sink	1	unit		
	18.1.2	Ground floor pantry sink counters 0.60x2.65m granite tile finish with sink	1	unit		
	18.1.3	lactating sink counters 0.60x2.35m granite tile finish with sink	1	unit		

		18.1.4	2nd floor pantry sink counters 0.60x3.13m granite tile finish with sink	1	unit		
		18.1.5	Female CR Lavatory counter top 0.60x1.70m	1	unit		
			SUB-TOTAL 18.0				
19.0	MECHANICAL WORKS						
	19.1	DRY TYPE STANDPIPE SYSTEM					
		19.1.1	Assorted GI pipe ASTM S-40	1	lot		
		19.1.2	Assorted GI fittings ASTM S-40	1	lot		
		19.1.3	Fire hose Valve 2-1/2"	2	pcs		
			fire hose cabinet 1 1/2" pressure regulating angle valve				
		19.1.4	1 1/2"x100' long double jacket fire hose with adjustable nozzle	2	set		

		19.1.5	siamese twin 2-1/2"	1	pcs		
		19.1.6	check valve 2-1/2"	1	pcs		
		19.1.7	Hangers and hanging accessories	1	lot		
		19.1.8	cutting and grinding disc	1	lot		
		19.1.9	QDE paint international red	1	gal		
		19.1.10	Paint thineer	1	gal		
		19.1.11	metal primer red oxide	1	gal		
		19.1.12	paint brush 3"	2	pcs		
		19.1.13	paint brush 2"	1	pcs		
		19.1.14	twine	1	rolls		
		19.1.15	gasket maker	1	tube		
		19.1.16	teflon tape 3/4"	1	pcs		
		19.1.17	steel brush	1	pcs		
		19.1.18	waste rugs	1	kg		
		SUB-TOTAL 19.0					
20.0	SIGNS AND SIGNAGES						
	20.1	Indoor Signages		1	lot		
		SUB-TOTAL 20.0					
21.0	HVAC						
	21.1	wall mounted split type aircon 2.5HP (inverter)		3	Sets		
	21.2	wall mounted split type aircon 2.0HP (inverter)		5	Sets		
	21.3	wall mounted split type aircon 1.5HP (inverter)		3	Sets		
	21.4	wall mounted split type aircon 1.0HP (inverter)		1	Sets		
	21.5	Condenser stand		12	Sets		
	21.6	wall type Exhaust Fans 14"		4	Sets		
		SUB-TOTAL 21.0					-
		GRAND TOTAL					

Submitted By:

Authorized Signatory

Date: